

Objectives

- Risk Assessment and Risk Management Offer a Systematic Approach to Understanding Uncertainties Surrounding Projects
- Objectives of Risk Management are to:
 - Identify strategies to mitigate risks
 - Take advantage of opportunities
 - Have sufficient funds (activity durations) to cover situations when things do not proceed as planned [establish sufficient contingencies]

Benefits of Risk Analysis

- A carefully planned risk analysis leads to:
 - Improved communication within project team
 - Improved external communication; helps to educate public and other parties
 - Better understanding of the project delivery process (timeline, phasing, obstacles)
 - More realistic estimates of project costs and durations

FTA's First Report on Risk Analysis




Causes of Cost Overrun (TCRP G-07 Study 2005)

- *Scope creep*
- Time required to achieve consensus among stakeholders and start construction
- Items left out of the estimate
- Uncertainty of real estate costs
- Inflation
- Project complexity
- Length of project development

Motivation

- In order to cope with cost overrun and delays, and identify risk factors early on, public transportation agencies have started using formal probabilistic risk assessment for their capital projects.
 - State of Washington D.o.T. (since 2002)
 - FTA (since 2003)
 - FHWA published a guide for risk analysis 2006
 - CALTRANS published a manual in 2007

Cost Uncertainty Over Project Life



It is important to realize that the cost estimate is not a single number; realistically it is a range!

Timing of Risk Assessment

Contracting Method	PROJECT PHASE			
	Conceptual Design*	Preliminary Engineering	Final Design	Construction
Design-Bid-Build	●	●	⊕	⊕
Design-Build	●	●	⊕	⊕
Design-Build-Operate-Maintain	●	●	⊕	⊕
Construction Manager/General Contractor	●	●	⊕	⊕

● Preliminary risk assessment based on conceptual cost and schedule data
 ● Comprehensive risk assessment based upon all the detailed information collected up to the point of analysis
 ⊕ Follow-up / updated risk assessment based upon most current design, cost, and schedule information.
 ⊕ Targeted risk assessment on special problems based upon all available information

Source: Parsons (2004)


Key Elements of Risk Analysis


• View the Process as 6 Steps



- First four steps are the process of *risk assessment*
- Last two are the process of *risk management*
- Risk analysis is not a static process; a feedback loop can alter the results
- Risk Management is a process of ongoing monitoring → reassessment → new mitigation efforts







Step 2. Risk Identification & Quantification

- **Objective:**
Identify Significant Project Risks and Estimate Individual Risk Impacts
- **Specific Tasks Include**
 - Prepare long list of potential risks for each major project component
 - Estimate impacts in terms of cost, delay
 - Screen significant risks
 - Document in risk register

2

RISK REGISTER

(Step 2. Risk Identification & Quantification)

Example of Risk Register Detail									
ID	Risk/Opportunity	Description of Issue	Affected Project Component	Correlation Among Dependent Components	Probability of Risk Occurring	Risk Cost		Risk Duration	
						Distribution	Expected Value of Cost	Distribution	Expected Value of Delay
1	Permitting and Interagency Agreements:	Permits required from approval agencies could be delayed; agreements between grantee and other agencies might not be concluded on schedule.	A. Design & Permitting D. Construction	Positive between Cost & Schedule of Both A & D	25% (0.25)	Triangular A. Design \$1.0 m = 10% \$2.0 m = Mode \$4.0 m = 90% D. Construction \$10.0 m = 10% \$30.0 m = Mode \$50.0 m = 90%	A. \$ 1.8 m D. \$21.0 m	Discrete A. Design 1 mos = 25% 2 mos = 50% 3 mos = 25% D. Construction 2 mos = 50% 5 mos = 40% 10 mos = 10%	A. 2 mos. D. 4 mos.
2	Utility Relocations:	Locations of certain utilities are unknown and their relocation could be required.	D. Construction		20%	Lognormal	\$5.0 m	Uniform 1.5 mos.-20%	6 mos.
3	Excess Ground Water Inflow	Estimated ground-water inflow in the tunnel may be too low. Dealing with excess water may increase the cost.	H. Tunnel	Positive between Cost & Schedule	50%	Lognormal	\$5.0 m	Lognormal	6 mos.

Expected Cost of Risk = Probability of Occurrence x Estimate of Risk Cost Impact

Step 3. Assessment (Modeling)

- **Objective:**
Estimate the Total Impact of Risk Factors on Total Project Cost or Duration
- **Specific Tasks:**
 - Identify most appropriate assessment method
 - Evaluate impacts on project by non-simulation or simulation methods
 - Verify results
 - Validate adequacy of project contingency

3


Risk Quantification

- Quantification is Typically a Multi-Step Process
 1. Estimate likelihood of risk occurring (10%? 90%?)
 2. Estimate range of values (\$/Time) if risk occurs. Values follow probability distributions.
 3. Establish correlations among risk events
 4. Estimate expected value of risk
 5. Document in Risk Register

16

Example of Data Modeling

- Estimator tells us that the cost of a building addition ranges between \$120 and \$210 per sq. ft. in Boston. This is assuming specific characteristics/performance criteria for the building.




Unit Cost per sq. ft.

17

Refinement of Information

- Estimator can further tell us that his best estimate of the unit cost would be \$150/sq.ft.
- We know that construction costs are usually unimodal, skewed distributions.



Unit Cost per sq. ft.

18

Example of Risk Modeling

Risk Factors for a Tunnel Project

A hypothetical tunnel project is under study.
 Three major risk factors are being considered:

- #1 – Excessive Groundwater inflow (low, medium, high)
- #2 – Total Rock Hardness (Estimated + 10, 20, 25)
- #3 – TBM breakdowns (Optimistic, pessimistic)

Risk Factors for Tunnel Project

Frequency (likelihood) vs Impact

- Excessive Groundwater
 - Probability of occurrence 40%
- Total Rock Hardness
 - Probability of occurrence 60%
- TBM breakdowns
 - Probability of occurrence 100%

Simulation Model of Risks

	Low	Mode	High	Random Input	Probability	Expected Value
Groundwater	\$ 300,000	\$ 700,000	\$ 1,500,000	\$ 833,333	0.4	\$ 333,333
Rock Hardness	\$ 1,500,000	\$ 2,500,000	\$ 3,800,000	\$ 2,600,000	0.6	\$ 1,560,000
TBM Breakdown	\$ -		\$ 4,000,000	\$ 2,000,000	1	\$ 2,000,000
					Total =	\$ 3,893,333

Step 4. Discussion / Review

- Objective:
Maintain open lines of communication; ensure that the Transportation Agency and other risk analysis participants agree on findings and on the next steps

4

- Review results of assessment
- Fully document findings

25

Risk Management

- Risk Management Includes
 - Steps 5 and 6 in the Risk Analysis Process, Covering
 - Risk Mitigation Planning (Step 5)
 - Risk Mitigation Implementation and Monitoring (Step 6)
 - Both Steps are Primarily Responsibilities of the transportation agency


26


Step 5. Risk Mitigation Planning

- Objective:
Develop Cost-Effective Mitigation Strategies to Reduce Risk Impacts to Project Budget and Schedule, Thereby Improving the Probability of Project Success

5

27





RISK MITIGATION PLAN (RMP)

- End Product of the RMP is a List of Targeted Risks
 - For each risk, establish actions to reduce impacts on total project cost or schedule
- Various Risk Mitigation Strategies Include
 - Avoid the risk
 - Share the risk
 - Reduce the risk
 - Transfer the risk
 - Accept the risk

Step 6. Implementation and Monitoring

- The Owner Must Implement and Monitor Mitigations

– Documents risk management program in Risk Management Plan (RMP), to include

6

- Objectives of the plan
- Prioritized list and description of risks for mitigation
- Description of risk management responsibilities of each party
- Performance monitoring program
- Implementation schedule
- Plan approval by executive management

31

U.S. FTA's Top-down Model


1. Finds Base cost (no contingency and escalation included) for each Standard Cost Category (SCC) of the FTA budget format:

Standard Cost Categories for Capital Projects	
Plan 1.16, June 2, 2009	
10.00000001 & 10.00000002 & 10.00000003	10.01000001
10.01000001	10.01000001
10.02000001	10.02000001
10.03000001	10.03000001
10.04000001	10.04000001
10.05000001	10.05000001
10.06000001	10.06000001
10.07000001	10.07000001
10.08000001	10.08000001
10.09000001	10.09000001
10.10000001	10.10000001
10.11000001	10.11000001
10.12000001	10.12000001
10.13000001	10.13000001
10.14000001	10.14000001
10.15000001	10.15000001
10.16000001	10.16000001
10.17000001	10.17000001
10.18000001	10.18000001
10.19000001	10.19000001
10.20000001	10.20000001
10.21000001	10.21000001
10.22000001	10.22000001
10.23000001	10.23000001
10.24000001	10.24000001
10.25000001	10.25000001
10.26000001	10.26000001
10.27000001	10.27000001
10.28000001	10.28000001
10.29000001	10.29000001
10.30000001	10.30000001
10.31000001	10.31000001
10.32000001	10.32000001
10.33000001	10.33000001
10.34000001	10.34000001
10.35000001	10.35000001
10.36000001	10.36000001
10.37000001	10.37000001
10.38000001	10.38000001
10.39000001	10.39000001
10.40000001	10.40000001
10.41000001	10.41000001
10.42000001	10.42000001
10.43000001	10.43000001
10.44000001	10.44000001
10.45000001	10.45000001
10.46000001	10.46000001
10.47000001	10.47000001
10.48000001	10.48000001
10.49000001	10.49000001
10.50000001	10.50000001

32

FTA's Top-down Model

2. Assumes that all cost items have Lognormal distributions; these distributions are quantified with two estimates:
 - 10th Percentile= Base Cost Estimate (BCE); 90th Percentile= BCE*β
3. A set of recommended β values is used (roughly 1.0 <β< 2.5);




33

Suggested Values for β

β	Project phase or state of risks
Larger than 2.5	Increasing uncertainty with project requirements. May need to increase the base.
2.0 - 2.5	At 2.0 Design risks have been mitigated.
1.75 - 2.0	At 1.75 all market risks including bidding risks have been mitigated.
1.35 - 1.5	All early construction risks such as geotech/utility/major claims have been mitigated (~20% construction)
1.35 - 1.20	All mid-construction risks inclusive of major claims, delays, impact have been mitigated
1.05 - 1.15	All startup/substantial completion risks, usually associated with 90% construction complete have been mitigated.
1.0	No risk or uncertainty is present.

Top-Down Analysis Outcome

4. The final outcome consists of three CDFs!



To recap...

- A carefully planned risk analysis leads to:
 - Improved communication within project team
 - Improved external communication; helps to educate public and other parties
 - Better understanding of the project delivery process (timeline, phasing, obstacles)
 - More realistic estimates of project costs and durations

